

NOTES:

- 1. MORTAR JOINTS SHALL BE 1/2 " MINIMUM THICKNESS WITH STAGGERED INTERLACED JOINTS.
- 2. HEIGHT OF VALLS SHALL BE A MINIMUM OF 12" OR A.O.B.E.
- 3. BRICK CATCH BASINS SHALL BE USED IN THE RIGHT-OF-WAY DUTSIDE THE PAVEMENT SECTION.
- 4. BRICK CATCH BASINS SHALL BE APPROVED IN ADVANCE BY M.C.D.O.T.





FIELD INLET - BRICK CATCH BASIN
NOT TO SCALE